

Integrated Security Corporation  
 Contract 900807  
 Price List  
 April 1, 2021

ITEM #	ITEM	DESCRIPTION	UNIT	PRICE
INFINITY 2020	Infinity 2020 Software	Data log retention of all activities, alarms/events, Sensitivity adjustments and arm/disarm function each zone individually from the central computer. No field adjustments required, wind and precipitation compensation for each	Each	\$3,700.00
INFINITY 2020U	Infinity 2020 Upgrade	Upgrade new software from Infinity 2000	Each	\$600.00
S-10	Sensor Cable	Fence-mounted cable with sensors.	Foot	\$7.00
S-9	Lead Cable	Cable to connect various system components.	Foot	\$1.50
JB-F	Junction Box	PVC, fence-mounted used to attach multiple zones of S-10 Sensor Cable	Each	\$65.00
TY-WRAP1	Nylon Ty-Wraps	Nylon UV and weather resistant to attach S-10 Sensor Cable to fence – 1,000 per bag.	Bag	\$85.00
TY-WRAP SS	Stainless Steel Ty-Wraps	Stainless Steel to attach S-10 Sensor Cable to fence – 1,000 per bag.	Bag	\$185.00
SG-1	Slide Gate Alarm	Assembly to incorporate slide gate into perimeter system.	Each	\$275.00
900501-A	Transponder Card	Monitors up to 8 zones of S-10 Sensor Cable	Each	\$1,250.00
900502	Controller Card	Monitors up to 8 transponder cards (64 zones)	Each	\$1,250.00
P-16	Processor Enclosure (Large)	Enclosure that includes power supply, battery backup, surge suppression and	Each	\$1,250.00
WX-75M	Weather Station	Monitors wind and precipitation conditions.	Each	\$750.00

1GATE-CN500	Magnetic Gate Contact	Allows alarm notification is the gate remains open	Each	\$75.00
MICRO-482/50	50M Microwave	482X Digital Microwave Barrier 50/M150 ft. with Fuzzy Logic Analysis and Ploe Clamps	Each	\$3,250.00
Computer	Computer	Computer to use with Infinity 2020 software	Each	\$1,500.00
Server	Server	Server to work with Infinity 2020 software	Each	\$3,200.00
UPS	UPS	Universal Power Supply for Computer	Each	\$200.00
Printer	Printer	Laser printer for event log	Each	\$275.00
IL-HE	Head-end: Processor and Infinity 2000 Installation	Head-end: Processor and Infinity 2000 Installation	Each	\$8,500.00
IL-WS	Weather Station Installation	Weather Station Installation	Each	\$1,300.00
IL-LC	Lead Cable Installation	Lead Cable Installation	Foot	\$1.00
IL-SL	Sensor Line Installation including Junction Boxes	Sensor Line Installation including Junction Boxes	Foot	\$2.75
IL-TW	Ty-Wrapping	Ty-Wrapping	Foot	\$0.75
IL-TO	Tear-out of Old System	Tear-out of Old System	Foot	\$0.25
IL-GC	Gate Contact Installation	Gate Contact Installation	Each	\$200.00
IL-SP	Sallyport Installation	Sallyport Installation	Each	\$8,300.00
IL-G	Gate Instalaltion	Gate Instalaltion	Each	\$500.00
IL-LR	Lift rental	Lift rental	Each	\$500.00
IL-PT	Proof & Test System and User Training	Proof & Test System and User Training	Each	\$2,500.00
IL-R	Repair	Repair of System	Hour	\$95.00
IL-TT	Travel time	Travel time to and from facility	Hour	\$45.00
IL-AB	As Built Drawings	As Built Drawings	Each	\$2,500.00
IL-MM	Mobile Map Installation	Mobile Map Installation	Each	\$4,580.00
VB	Vision Board	Monitors up to 16 zones of S-10 Sensor Cable	Each	\$1,650.00

SIB	Sensor Interface Board	Interface for field connections and surge suppression	Each	\$450.00
RB	Relay Board	Zone alarm output relays for external systems, 2 per zone	Each	\$400.00
ZS	Zone Sign	Zone Sign	Each	\$75.00
MP2500	Receiver/Display (8-zone).	Receiver/Display (8-zone).	Each	\$2,859.29
MP2510	Additional 8-Zone Modules.	Additional 8-Zone Modules.	Each	\$398.97
MP1000	Display Artwork.	Display Artwork.	Each	\$825.00
MP1500	Basic 8-Zone.	Basic 8-Zone.	Each	\$1,529.39
MP1510	Additional 8-Zone Adder	Additional 8-Zone Adder	Each	\$119.16
TE125	Power Supply.	Power Supply.	Each	\$86.45
MP3500	Transmitter Module.	Transmitter Module.	Each	\$2,175.00
MP2015	Higher Gain Stick.	Higher Gain Stick.	Each	\$387.38
MP150	RG-8 Low Loss Assembly.	RG-8 Low Loss Assembly.	Each	\$55.61
MP152	Low Loss Cable per Foot.	Low Loss Cable per Foot.	Each	\$2.10
MP1610	Mobile Map Antenna Assembly.	Mobile Map Antenna Assembly.	Each	\$84.00
TE100	Accessory Mobile Unit Mount.	Accessory Mobile Unit Mount.	Each	\$166.84